Final Plat
Lots 62–111

Sundance Estates

an Addition to the City of Lubbock, Lubbock County, Texas

VOL 16 PAGE 25-B

VOL 16 PAGE 25-A

STATE OF TEXAS
REGISTERED
J. M. CIESZINSKI
4460
PROFESSIONAL
LAND SURVEYOR

KNOW ALL MEN BY THESE PRESENTS

That I, JONATHAN MARK CIESZINSKI, Registered Professional Land Surveyor do hereby certify that I prepared this plat from an actual and accurate survey of the land and the corner monuments shown thereon were properly placed under my personal supervision in accordance with the Subdivision Regulations of the City of Lubbock, Texas.

REGISTERED PROFESSIONAL LAND SURVEYOR, # 4460 LUBBOCK, TEXAS
May 10, 2019
Revised October 12, 2020 (SPEC Easements, Perimeter, Adjoining Owners)
Revised November 5, 2020 (Changed lala to Huron)

CONTAINS 32.89 ACRES WITHIN THE PLAT LIMITS

ALL ALLEYS ARE 20' IN WIDTH

LPL – LUBBOCK POWER, LIGHT AND WATER CO.
AT&T – AT&T TELEPHONE COMPANY
UUE – UNDERGROUND UTILITY EASEMENT
EASEMENT
PVT – PRIVATE
TR – TRANSFORMER PAD EASEMENT, 4' X 6' (NOT DRAWN TO SCALE)
SWBT – SOUTHWESTERN BELL TELEPHONE CO.
WLE – WATER LINE EASEMENT
DRE – DRAINAGE EASEMENT
DUE – DRE and UUE CENTERED ON LOT LINE WHERE APPLICABLE
USE – UNDERGROUND STREET LIGHT CABLE EASEMENT
ACE – 5' ACCESS EASEMENT AND 2' EAVE OVERHANG EASEMENT
PAE – PEDESTRIAN ACCESS EASEMENT
SEE – SWITCH ENCLOSURE EASEMENT, 6' X 6' (NOT DRAWN TO SCALE)
CCFN – LUBBOCK COUNTY CLERK FILE NUMBER

A METES AND BOUNDS DESCRIPTION OF THIS TRACT WAS PREPARED FOR RECORDATION WITH THE DEDICATION DEED OF THIS TRACT.

Survey Control: Bearings and Coordinates are based on the Texas North Central Zone Coordinate System, NAD 83, 2011, EPOCH 2010.0000. Coordinates determined by OPUS Observations.

Any easements or rights-of-way shown as 'to be dedicated by separate instrument' are shown on this plat for information purposes only. This plat does not dedicate said easements.

1/2" Iron Rod with Green Cap marked RPLS 4460 found or set at all block corners and control points.

APPROVED this July Day of 2nd, 20 19 by the PLANNING AND ZONING COMMISSION of the CITY of LUBBOCK

APPROVED _____ CHAIRMAN

ATTEST _____ SECRETARY



SCALE: 1"=100'
HEAVY LINES INDICATE PLAT LIMITS.
ALL STREETS, ALLEYS, AND EASEMENTS WITHIN PLAT LIMITS ARE HEREIN DEDICATED.
ALL EASEMENTS DEDICATED HEREBY SHALL ENTITLE THE CITY OR THE UTILITY COMPANY USING SUCH EASEMENTS TO THE RIGHT TO REMOVE, REPAIR, OR REPLACE ANY LINES, PIPES, CONDUITS, OR POLES WITHIN SUCH EASEMENTS AS MAY BE DETERMINED BY THE CITY OR THE UTILITY COMPANY WITHOUT THE CITY OR THE UTILITY COMPANY BEING RESPONSIBLE OR LIABLE FOR THE REPLACEMENT OF IMPROVEMENTS, PAVING, OR SURFACING OF THE EASEMENT NECESSITATED BY SUCH REMOVAL, REPAIR, OR REPLACEMENT. EASEMENTS DESIGNATED OR INTENDED FOR VEHICULAR PASSAGE (UTILITY AND EMERGENCY) OR PEDESTRIAN ACCESS SHALL NOT BE FENCED OR OTHERWISE OBSTRUCTED.
ALL ELECTRICAL SERVICE SHALL BE IN ACCORDANCE WITH THE UNDERGROUND UTILITIES POLICY STATEMENT BY THE PLANNING AND ZONING COMMISSION OF THE CITY OF LUBBOCK, TEXAS.
ANY RELOCATION OR REVISION OF EXISTING FACILITIES SHALL BE AT THE DEVELOPER'S EXPENSE. COMPENSATION SHALL BE MADE PRIOR TO RECORDING OF ANY PORTION OF THIS PLAT.
ALL EXISTING OR PROPOSED UTILITY SERVICES TO AND ON TRACTS INDICATED BY THIS PLAT SHALL BE CONTAINED IN THE PUBLIC RIGHT-OF-WAY AND PUBLIC OR PRIVATE UTILITY EASEMENTS. UTILITY SERVICE INSTALLATION REQUESTED AT A FUTURE DATE, AND NOT WITHIN AN EASEMENT INDICATED BY THIS PLAT, SHALL BE WITHIN A PROPER UTILITY EASEMENT GRANTED BY THE OWNER OF SAID PROPERTY BY SEPARATE RECORDED INSTRUMENT PRIOR TO THE PROVISION OF SUCH SERVICE. SUCH EASEMENTS SHALL BE AT THE DEVELOPER'S EXPENSE.
NO BUILDING PERMIT SHALL BE ISSUED ON ANY SURVEY CERTIFICATE THAT IS NOT IN ACCORDANCE WITH AN APPROVED FINAL PLAT UNLESS AN EXCEPTION IS PROVIDED BY PLANNING COMMISSION POLICY OR BY THE LUBBOCK CODE OF ORDINANCES.
MINIMUM FINISH FLOOR SHALL CONFORM TO THE REQUIREMENTS OF THE LUBBOCK DRAINAGE CRITERIA MANUAL, AS ADOPTED BY RESOLUTION NO. 10022, AND SECTION 28.09.131, SECTION 28.14.004 AND SECTION SECTION 30.03.073 OF THE LUBBOCK CODE OF ORDINANCES.

ABACUS ENGINEERING SURVEYING
2737 81st Street
LUBBOCK, TEXAS
Count on It 806-745-7670
TEXAS SURVEYING FIRM NO. 101153-00
TEXAS ENGINEERING FIRM NO. 4368